000903

MEZZANINE FLOOR PLAN · OFFICE BUILDING

FIN. FL. ELEV. 989'-0"

1/8" = 1'-0"

STUDENT WAITING & STUDY AREA M-110

SEMINAR ROOM M-145

UPPER MAIN LOBBY 101

ELEVATOR LOBBY M-100

WOMENS TOILET M-110A

MENS TOILET M-110B

POWDER M-110C

PREP R.M. M-145A

DUCT SPACE "E"

DUCT SPACE "F"

PIPE SPACE NO 1

PIPE SPACE NO 2

STAIR NO 1

STAIR NO 2

ELEV. NO 1

ELEV. NO 2

ELEV. NO 3

ELEV. NO 4

ELEC. SHAFT

E.W.C.

T.R.

F.E.C.

GRILLE (SEE MECH.)

GUARDRAIL (DET. DWG T-4)

GUARDRAILS (DET. DWGS T-4)

WOOD HAND RAIL (SPEC. SECT. 10-5) ON METAL RAIL (SPEC. SECT. 5-3)

WOOD STRIP (SPEC. SECT. 10-5)

WIRE SHELVING (SPEC. SECT. 10-5)

SEE REVISED DWG SP-12

SEE ENLARGED PLAN DWG. E-12

CHALKBOARD - TYPE "E" SEE SCHED. ON DRWG. G-9

SEE ENLARGED PLAN DWG. G-12

WOOD WALL CAP (SPEC. SECT. 6 & 9) (OMIT VIA DWG. G-11)

FACE OF CONC.

WALL LINE 15½" EAST OF CG'D

WALL LINE 15½" WEST OF CG'D

WALL LINE 15½" NORTH OF CG'D

WALL LINE 15½" SOUTH OF CG'D

NOTE: SEE DWG. G-11 FOR DETS. STAIR, WALLS, ETC. IN THIS AREA

18 MODULES @ 5'-0" = 90'-0"

26 MODULES @ 5'-0" = 130'-0"

99'-0"

FIRST FLOOR PLAN · OFFICE BUILDING

FIN. FL. ELEV. 979'-0"

1/8" = 1'-0"

SEMINAR ROOM 110 (SUSPENDED CEILING)

SECONDARY LOBBY 104

SEMINAR ROOM 112 (SUSPENDED CEILING)

SEMINAR ROOM 145

WEST LOBBY 103

EAST LOBBY 105

CORRIDOR 102 (SUSPENDED CEILING)

CORRIDOR 106 (SUSPENDED CEILING)

SEMINAR ROOM 108 (SUSPENDED CEILING)

MAIN LOBBY 101

SEMINAR ROOM 107 (SUSPENDED CEILING)

STAIR NO 3

STAIR NO 4

ELEV. NO 1

ELEV. NO 2

ELEV. NO 3

ELEV. NO 4

ELEV. NO 5

ELEV. NO 6

DUCT SPACE "E"

DUCT SPACE "F"

DUCT SPACE "G"

DUCT SPACE "H"

PREP R.M. 112-A

PREP R.M. 145-A

JAN. CL. 112

JAN. CL. 145

CHALKBOARD - TYPE "E" SEE SCHED. DRWG 9

TYPE "B" BENCHES - BASE DET. DWG G-15

DOOR GUARDS (SPEC. SECT. 10-5) SEE DRWG. T-4

BREAK GLASS FIRE ALARM STATION SPEC. SECT. 16

DESK BASE DETS. ON DRWG. CHS & O-10

PLANTER - SEE DETS. ON DRWG. O-15

WOOD GRILLE (DET. DWG T-6)

SUSP. AC TILE CLG (SPEC. SECT. 9E)

SUSP. GYP. BD. CLG (SPEC. SECT. 9D)

SUSP. ACOUS. TILE CEILING

SUSP. GYP. BD. CEILING

F.E.C. (SPEC. SECT. 10-18)

D.W.P. (SPEC. SECT. 6B) DET. DWG. G-11

CARPET (SPEC. SECT. 12)

26 MODULES @ 5'-0" = 130'-0"

99'-0"

ROOM FINISH SCHEDULE

ROOM NO	ROOM NAME	FLOOR: RESILIENT TILE	FLOOR: CERAMIC TILE	FLOOR: TERRAZZO	FLOOR: CARPET	FLOOR: CONC PAINTED	BASE: CERAMIC TILE	BASE: NONE PAINTED	BASE: VINYL (COVE)	WALLS: BRICK	WALLS: CONC. BLOCK	WALLS: CONCRETE	WALLS: CERAMIC TILE	WALLS: WOOD	WALLS: WALL COVERING #1	WALLS: WALL COVERING #2	WALLS: METAL	CEILING HEIGHT	CEILING: ACOUS TILE A	CEILING: ACOUS TILE D	CEILING: ACOUS TILE E	CEILING: CONCRETE G	CEILING: H.W. PLASTER J	REMARKS
100, M-100	ELEVATOR LOBBIES	●				●		●	2½" VINYL (S1A)			●						*				●		* 100 M-100 8'-2" ⑦
101	MAIN LOBBY, STAIR NO 3 & 4	●				●		●	2½" VINYL (S1A)			●						8'-4¾"	●					
102, 106	CORRIDORS	●				●		●	2½" VINYL (S1A)			●						—				●		
103, 105	EAST & WEST LOBBIES	●				●		●	2½" VINYL (S1A)			●						8'-4¾"	●					
104	SECONDARY LOBBY	●				●		●	2½" VINYL (S1A)			●						8'-4¾"	●					
107, 108, 110, 113	SEMINAR ROOMS		●		●		●		2½" VINYL (COVE)				●					8'-4¾"		●				
109, 116, M-109	JANITOR CLOSETS		●				●						●											
114, 112A, 115A	PREPARATION ROOMS	●					●						●					8'-4¾"		●				
111, 147	ELECT. CLOSETS					●		●				●						*				●		* 112, 145 M-145 8'-2"
112, 145, M-145	SEMINAR ROOMS		●		●		●		2½" VINYL (COVE)				●							●				
M-110	STUD. WAIT. & STUDY				●			●										8'-0"			●			SEE ENLARGED TOILET PLAN DWG. T-2
M-110 A & B	MEN & WOMEN		●				●						●					8'-0"			●			
M-110C	POWDER ROOM		●				●						●											
	STAIR NO 1 & 2	●				●		●				●						6'-10"				●		⑤ SEE DWG. T-12
145-A, M-145A	PREPARATION ROOMS	●				●		●				●												

⑦ TERR. FL. IN 100 - CARPET IN M-100. ⑧ TERRAZZO 1ST FL. - RES. TILE MEZZANINE FL.

FIRST & MEZZANINE FLOOR

SECOND FL. ELEV. 999'-0"

FIN. FL. ELEV. 989'-0"

COURSES - 8'-0"

DOVETAIL SLOTS @ 5'-0" O.C. (SPEC. SECT. 4A)

TYPICAL DOVETAIL SLOT & ANCHOR AT ALL EXTERIOR ACOUS. TILE & BRICK

SECTION D 3/4" = 1'-0"

PLAN L

PLAN W

SECTION E 3/4" = 1'-0"

SECTION F HALF SIZE

SECTION G 3/4" = 1'-0"

SECTION H 3/4" = 1'-0"

SECTION J 3/4" = 1'-0"

SECTION K 3/4" = 1'-0"

TYP WALL ANCHORAGE DETAILS 3/4" = 1'-0" DT.S. & A = DOVETAIL SLOT & ANCHOR

ELEVATION OF TYP. THERMOSTAT RECESS - LOCATE WHERE T.R. NOTED ON FLOOR PLANS 1½" = 1'-0"

SECTION A 1/4" = 1'-0"

SECTION B 1/4" = 1'-0"

SECTION C 1/4" = 1'-0"

SECTION M 3/4" = 1'-0"

SECTION N 3/4" = 1'-0"

STAIR NO 2

GLASS WALL

GUARDRAIL (DET. DWG T-4)

GLASS

BRICK

GRILLE (SEE MECH.)

SUSP. AC TILE CLG (SPEC. SECT. 9E)

MEZZ. FL. ELEV. 989'-0"

FIRST FL. ELEV. 979'-0"

2" INSULATION (SPEC. SECT. 7B)

CORNERSTONE DET. DWG. T-6

1967

D.W.P. DET. DWG. B-11

CIG. URN

F.E.C. (SPEC. SECT. 10-5)

STAIR NO 3

STAIR NO 4

SEE STAIR SECTION DWG. O-15

F.H.C. (SPEC. SECT. 15)

EXIT LT. (SPEC. SEC. 16)

TERRAZZO FL. FIN. 5" TH.

FLOURESCENT LUMIN., FSE CONT. FLEX. CONDUIT IN LUMINOUS CEILING (SPEC. SECT. 10-8)

DUCT SPACE "F"

DUCT SPACE "G"

CONC.

T.R.

LIGHT SWITCH

E.W.C. (SPEC. SECT. 19)

DECORATIVE WALL PANEL DET. DWG. G-11

TYP.

CONC. INSERT (SPEC. SECT. 9)

SUSP. AC. TILE CLG

PROJECT NO. KY 2-1555

1ST. & MEZZ. FL. PLANS & FIN. SCHED.

GENERAL CLASSROOM-OFFICE BUILDING

UNIVERSITY OF KENTUCKY, LEXINGTON, KENTUCKY

SPEC. NO. 6605	JOHNSON — ROMANOWITZ ARCHITECTS LEXINGTON KENTUCKY	DRAWING NO. O-2
DRAWN BY RCB		
CHECKED BY J-R	COMMONWEALTH OF KENTUCKY DEPARTMENT OF FINANCE ENGINEERING STAFF FRANKFORT KENTUCKY	TOTAL SHEETS 137
REVISIONS		DATE DEC. 1966

APPROVED BY _____ DISTRICT HEAD — DATE 1/6/67

APPROVED BY _____ CHIEF OF STAFF — DATE

BYRON F. ROMANOWITZ REGISTERED Reg. No. 472 COMMONWEALTH OF KENTUCKY ARCHITECT

ERNST VERN JOHNSON REGISTERED Reg. No. 1557 COMMONWEALTH OF KENTUCKY ARCHITECT

IN ELEC. CLG ADDED PLYWD ON WALLS FOR TELEPHONE EQUIP. MOVED STAIR DWGS # 1 & 2

MONTANA'S N. ... 1967 ... 4 ... 137